



WCORD RIVER
FLOW
587.90'

- ### PLANTING NOTES
1. THE CONTRACTOR SHALL SUPPLY ALL PLANT MATERIALS IN QUANTITIES SUFFICIENT TO COMPLETE THE PLANTINGS SHOWN ON THE DRAWINGS.
 2. ALL PLANT MATERIALS SHALL CONFORM TO GUIDELINES ESTABLISHED BY THE AMERICAN STANDARD FOR NURSERY STOCK, PUBLISHED BY THE ASSOCIATION OF NURSERMEN, INC.
 3. ALL PLANTS SHALL BE BALLED AND BURLAPPED OR CONTAINER GROWN UNLESS OTHERWISE NOTED ON THE PLANT SCHEDULE.
 4. ALL PLANTS ARE TO BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
 5. STAKE LOCATIONS OF ALL PLANTINGS FOR APPROVAL BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
 6. CONTRACTOR SHALL LOCATE AND VERIFY ALL UTILITY LINES PRIOR TO PLANTING AND SHALL REPORT CONFLICTS WHICH OCCUR TO THE LANDSCAPE ARCHITECT.
 7. ANY PROPOSED SUBSTITUTIONS OF PLANT SPECIES WILL BE MADE WITH PLANTS OF EQUIVALENT OVERALL FORM, HEIGHT, BRANCHING HABIT, FLOWER, LEAF, FRUIT, AND CULTURE AS APPROVED BY THE LANDSCAPE ARCHITECT.
 8. NO EXISTING TREES OR SHRUBS ARE TO BE REMOVED BY THE PLANTING CONTRACTOR WITHOUT PRIOR APPROVAL BY THE LANDSCAPE ARCHITECT.
 9. ALL AREAS DISTURBED DURING CONSTRUCTION BOTH OUTSIDE LIMIT OF WORK AND WITHIN SHALL BE RESTORED TO ORIGINAL CONDITION.
 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR WATERING ALL PLANTINGS AND SEEDS AREAS FOR THE DURATION OF THE CONTRACT INCLUDING THE MAINTENANCE PERIOD SPECIFIED.
 11. THE CONTRACTOR SHALL ESTABLISH A FINAL INSPECTION/DATE OF ACCEPTANCE MEETING WITH THE LANDSCAPE ARCHITECT. PLANT MATERIALS SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FOLLOWING ACCEPTANCE. ALL DEAD AND UNSATISFACTORY MATERIALS SHALL BE REMOVED AND REPLACED WITH MATERIALS OF SIMILAR TYPE AND SIZE. REPLACEMENT MATERIALS SHALL BE GUARANTEED FOR ONE YEAR FROM DATE OF ACCEPTANCE.
 12. THE CONTRACTOR SHALL STRIP LOAM AND STOCKPILE. LOAM SHALL BE AUGMENTED AS NEEDED AND SPREAD TO A DEPTH OF 4", RAKED CLEAN OF STONES AND SEEDS ACCORDING TO SPECIFICATIONS.

CONT. ON
SHEET NO. 27

PLANT LIST: AREA 1 - RED LOCK AREA

ITEM #	QTY.	BOTANICAL NAME	COMMON NAME	SIZE
773,141	15	Pinus thunbergii	Pine - Japanese Black	8-10'
773,408	7	Pinus cembra	Pine - Swiss Stone	5-6'
771,439	12	Pinus strobus	Pine - Eastern White	10-12'
775,055	0	Carpinus betulus 'Fastigiata'	Hornbeam - Fastigiata	2 1/2" - 3" CAL
776,545	3	Acer rubrum 'October Glory'	Red Maple - 'October Glory'	2 1/2" - 3" CAL
777,042	2	Quercus borealis rubra	Oak - Northern Red	2 1/2" - 3" CAL
777,745	2	Salix babylonica	Willow - Weeping	3' - 3 1/2'
777,749	0	Salix Sericea 'Silver Column'	Willow - Yellow Weeping	2 - 2 1/2' CAL
777,549	0	Platanus acerifolia 'Bloodgood'	Platanus - London	2 1/2" - 3" CAL
778,167	0	Betula nigra 'Riverit'	Birch - River 'Heritage'	20' - 22' CLUMP
778,459	0	Malus Red Baron	Cherry - Hegan - Weeping	2 1/2" - 3" CAL
778,449	9	Malus Red Baron	Crabapple - Red Baron	2 1/2" - 3" CAL
778,459	0	Malus 'Sentinel'	Crabapple - Sentinel	2 1/2" - 3" CAL
781,027	0	Chionanthus virginicus	Plumb Tree - 'Thundercloud'	2 1/2" - 3" CAL
782,477	0	Prunus cerasifera 'Thundercloud'	Shad Tree - A	2 1/2" - 3" cal
783,043	3	Ameibachia laevis	Yellowwood	2 1/2" - 3" CAL
783,541	0	Cedrasils lutea	Zelkova - 'Village Green'	2 1/2" - 3" CAL
785,741	23	Ilex glabra 'Shamrock'	Inkberry - 'Shamrock'	3' - 3 1/2'
786,375	8	Juniperus chinensis 'Mint Julep'	Juniper - Mint Julep	24-30 inch
786,673	14	Juniperus chinensis 'Pfitzerana'	Juniper - Pfitzer Compact	3' - 3 1/2'
787,082	7	Kalmia latifolia	Mountain Laurel	3' - 3 1/2'
790,635	22	Cornus sericea	Rhododendron maximum	3' - 3 1/2'
791,315	28	Fothergilla gardenii	Dogwood Redstart	3' - 3 1/2'
794,634	24	Rhus typhina	Fothergilla - Dwarf	2 1/2" - 3"
794,805	15	Comptonia peregrina	Sweetfern	5-6'
795,197	15	Hamamelis vernalis	Witch Hazel - Spring Blooming	2 gallon
765,000		Seeding - Lawns	000 SY	
765,200		Seeding - Erosion Control	12,459 SY	
765,700		Seeding - Wild Flower	10,507 SY	
765,800		Seeding - Low Mow	11,012 SY	

